BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/08/2012-13 Dated: 13-12-2013

APPROVED TENDER SCHEDULE –'B'

Item No: 33

Name of Work:-Providing RCC covering to Existing SWD at kamakshamma layout 1st main road near chinnappa house in ward No-02 of yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri DANANJAYA B R	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	134.20	148.33	Rupees one hundred forty eight and paise thirty three only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRS M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance	Sqm	134.20	76.48	Rupees seventy six and paise forty eight only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS	Cum	33.85	4194.30	Rupees four thousand one hundred ninety four and paise thirty only
4	KSRB 5.2-2 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with mud mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	43.50	3470.09	Rupees three thousand four hundred seventy and paise nine only
5	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification.	Cum	37.19	4671.47	Rupees four thousand six hundred seventy one and paise forty seven only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri DANANJAYA B R	
				Rate	Rate in Words
6	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	42.00	78.12	Rupees seventy eight and paise twelve only
7	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification	Cum	71.40	5512.87	Rupees five thousand five hundred twelev and paise eighty seven only
8	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification	Cunt	64.26	7210.96	Rupees seven thousand two hundred ten and paise ninety six only
9	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification	Sqm	340.00	264.30	Rupees two hundred sixty four and paise thirty only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.